BRUHAT BANGALORE MAHANAGARA PALIKE

NEGOTIATION SCHEDULE - B

BBMP/2014-15/OW/WORK_INDENT16530

Excavation for Temporary immersion Tank for Lord Ganesh idoles in ward no. 10 Doddabommasandra Vidyaranyapura sub division.

Sl. No.	Approved Qty.	Description	Unit	Negotiation Tender Rates of R S THYAGARAJ	
				In Figures	In Words
1	42	Earth work in surface excavation in hard soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed etc complete as per specifications and directions of engineer in charge of the work	Cum	199.39	Rupees One Hundred Ninety Nine and Thirty Eight Paise Only
2	214.5	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	257.10	Rupees Two Hundred Fifty Seven and Ten Paise Only
3	214.5	Above 1.5 Mtrs Depth Add 25% Extra	Cum	245.30	Rupees Two Hundred Forty Five and Thirty Paise Only
4	820	Code 0516 - Providing Plastic Sheet etc complete as per specifications and directions of engineer in charge of the work	Sqm	4.95	Rupees Four and Ninety Five Paise Only
5	165	Supply of water Through water Tank for filling Tank etc complete as per specifications and directions of engineer in charge of the work	Each	346.50	Rupees Three Hundred Forty Six and Fifty Paise Only
6	12.5	Providing Stone dust to approach road and near immersion tank for levelling and to protect not to sliping Sl No. 50 Code 400 metal Component etc complete as per specifications and directions of engineer in charge of the work	Cum	178.20	Rupees One Hundred Seventy Eight and Twenty Paise Only
7	66	Hire charge of pumping water 3.5 KL/hr capacity Pump etc complete as per specifications and directions of engineer in charge of the work	Hr	34.65	Rupees Thirty Four and Sixty Five Paise Only
8	165	Engaging unskilled heavy Mazdoor laboru for Guarding and for helping the public to immersion tank Ganesh Idols and to safe guard the public during the pooja Time etc complete as per specifications and directions of engineer in charge of the work	Days	181.41	Rupees One Hundred Eighty One and Forty Paise Only
9	3355	Hire Charges for Two Tier Barricading with casurens poles at 2.50mtrs C/C vertically and 0.50 mtrs C/C Horizontaly with Necessary earth work and labour etc complete as per specifications and directions of engineer in charge of the work	Rft	16.83	Rupees Sixteen and Eighty Three Paise Only
10	13200	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 40ft x 30ft = 1200 sqft) etc complete as per specifications and directions of engineer in charge of the work	Sft	2.97	Rupees Two and Ninety Seven Paise Only

ಸ.ಆ. (ಪೂರ್ವ)

Sl. No.	Approved Qty.	Description	Unit	Negotiation Tender Rates of R S THYAGARAJ	
				In Figures	In Words
11	550	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft) etc complete as per specifications and directions of engineer in charge of the work	Rft	16.83	Rupees Sixteen and Eighty Three Paise Only
12	550	Hire Charge for Armless Plastic Chairs etc complete as per specifications and directions of engineer in charge of the work	Nos	3.96	Rupees Three and Ninety Six Paise Only
13	110	Hire Charge for Wooden Table of Size 6ft x 2ft etc complete as per specifications and directions of engineer in charge of the work	Nos	39.60	Rupees Thirty Nine and Sixty Paise Only
14	2200	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathe daluminium wire etc complete as per specifications and directions of engineer in charge of the work	Mtrs	8.91	Rupees Eight and Ninety One Paise Only
15	88	Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges etc complete as per specifications and directions of engineer in charge of the work	Hr	556.38	Rupees Five Hundred Fifty Six and Thirty Eight Paise Only
16	154	Hire chargesfor Flood lighting arrangements for the stage and existing immersion Tank during night time etc complete as per specifications and directions of engineer in charge of the work	Nos	282.15	Rupees Two Hundred Eighty Two and Fifteen Paise Only
17	6	Hire charges compoment name 1087 Crane charges etc complete as per specifications and directions of engineer in charge of the work	Day	3168.00	Rupees Three Thousand One Hundred Sixty Eight Only
18	429	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour etc complete as per specifications and directions of engineer in charge of the work	Cum	70.57	Rupees Seventy and Fifty Six Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92